



DEPARTMENT OF GENERAL SERVICES
BUREAU OF BUILDING CONSTRUCTION

PINEY RUN WASTEWATER PUMP STATION UPGRADE

Project Summary

The design and construction of a 7.5 MGD Upgrade to the existing Piney Run Pump Station in Sykesville, Maryland. The project will include, but not limited to, two new electric motor-driven pumps, each of 850 gallons per minute (gpm) capacity; two liquefied petroleum gas (LPG) – fueled engine-driven pumps providing a total capacity of 5,250 gpm when operating simultaneously; an LP storage system; interior and exterior wastewater piping modifications; wastewater grinder system modifications; electrical power and control system improvements; plumbing, heating, and ventilation system improvements; pump station building structural modifications, and pump station site improvements.

Parcel Information

- ✚ Street Address: 7235 Brangles Road, Sykesville, Maryland
- ✚ Acreage: ~ 1.5 acres
- ✚ Tax Map 73, Parcel 764
- ✚ Election District 05
- ✚ Zoning: Exempt Commercial

Operator(s)

- ✚ Carroll County/Dept. of Public Works

Project Engineer

- ✚ Gannett Fleming, Inc.

Design/Build Contractor

- ✚ Conewago Enterprise, Inc. with GMB Architect/Engineering

Project Timeline

- ✚ Design to be completed approximately 7/10
- ✚ Construction start is scheduled for 8/10
- ✚ Targeted project completion is 4/11

Budget

- ✚ The construction budget for the project is \$ 2.5 M

Contact Information

- ✚ Scott Moser, Bureau Chief, Carroll County Bureau of Building Construction;
Telephone No. 410-386-2248